

Request for Proposal

Notice:

Mineral Area College, 5270 Flat River Rd., Park Hills, MO 63601, will accept proposals for Roof Duct replacement in the Bob Sechrest Fieldhouse. Work will include ductwork per SMACNA standards, Demolition of old ductwork, rework existing duct supports, phasing of installation, hoisting cost be included, all work done during normal work hours M-F, one year material and labor warranty for all ductwork, certified payroll for all field labor. Proposal should exclude overtime to perform work and taxes, bonds, fees, and permit costs. Organizations are invited to submit three (3) copies of a formal proposal and one (1) digital copy. Proposals should address the ability to provide all site work. Responses to this RFP must be received at the President's Office, 5270 Flat River Rd., Park Hills, MO 63601, (jgilgour@mineralarea.edu for the digital copy), prior to 2 p.m. on Friday, August 29, 2025. Questions may be directed to the General Services Director, Rodney Resinger (rresinger@mineralarea.edu).

- Replacement ductwork to have same internal dimensions as existing ductwork
- All ductwork to have 2" thick tough guard liner insulation
- Fabrication static pressure to be 4"
- All ductwork to be TDF flanged ductwork
- All ductwork to be sealed at flanges
- Continuous flange clip to cover complete top mating flanges on all top joints
- Seal ductwork as it enters the building and at the unit
- Remove offsite and dispose of old ductwork
- On phasing, coordination with owner is a must, downtime must be minimized.
- Unit cannot be down for any long length of time
- Ductwork to be install in large sections, then hoisted into place